

QUOTATION FOR SERVICES FOR RATE CONTRACT FOR NEW INSTALLATION/EXTENSIONS					
S.No.	Description	Unit	Unit price	Estimate Required Qty	Accepted Brands
1	Supply & Laying Charges of CAT 6 Cable	p. mtr.		5000	Dlink, Amp
2	Termination of UTP Cable: Ferruling/ Testing/ Cable Identification/ Termination of UTP CAT 6 cable on Information Outlet / Jack Panel/ with RJ45. Proper Cable labeling at front of SMB & Jack Panel/ Cable Dressing	nos.		50	
3	Supply & Installation of Information Outlet (Single SMB)	nos.		50	Dlink, Amp
4	Supply & Installation of Jack panel- 24 port - UTP CAT -6 complied (independent)	Each (per Panel of 24 Ports)		5	Dlink, Amp
5	Supply & connecting JP to Switch ports - Patch Cord -3 ft	Nos.		60	Dlink, Amp
6	Supply & Connecting Information Outlets to computers/ Printer, etc. - Patch Cord - 7 ft	Nos.		25	Dlink, Amp
7	Supply & Connecting Information Outlets to computers/ Printer, etc. - Patch Cord - 10 ft	Nos.		25	Dlink, Amp
8	Supply, Installation & Fixing of P.V.C. Duct (25 X 15 mm)	p. mtr.		1000	
9	Supply, Installation & Fixing of P.V.C. Duct (30 X 25 mm)	p. mtr.		2000	
10	Supply, Installation & Fixing of P.V.C. Duct (15 X 15 mm)	p. mtr.		2000	
11	Supply, Installation & Fixing of HDPE pipe (1.5 dia)	p. mtr.		1000	
12	Digging & Refilling of soft/hard soil or concrete (upto 1 mtr deep.) for laying Underground UTP Cable.	p. mtr.		1000	
13	Supply & Installation of Unmanaged Switch (8 ports) with 1 yr warranty	per piece		5	Dlink, TP link

14	Supply & Installation of Unmanaged Switch (16 ports) with 1 yr warranty	per piece		5	Dlink, TP link
15	Supply & Installation of Unmanaged Switch (24 ports) with 1 yr warranty	per piece		5	Dlink, TP link
16	Supply & installation of NETWORK RACK, DIMENSION : WIDTH : 19 IN, HEIGHT : 12U, ADDITIONAL INFORMATION : WALL MOUNT, 24 PORT PATCH PANEL, FRONT DOOR WITH LOCK, 2 COOLING FAN, 1 POWER DISTRIBUTION BOX, 1 CANTILEVER TRAY WITH HARDWARE FIXING SCREW with proper labelling & management of cables	per piece		5	Comrack/ HCL/ Dlink